

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Rice County. Sec. 6 Twp. 19 Rge. 10W E/W
Location as "NE/CNW 1/4 SW 1/4" or footage from lines
SE SW NW


Lease Owner Tiverton Petroleum, Inc.
Lease Name RINGWALD Well No. 1
Office Address #209-603 7th Ave., Calgary, Alberta,
Character of Well (Completed as Oil, Gas or Dry Hole) Canada
Dry Hole

Date Well completed 06/29/1981
Application for plugging filed 06/29/1981
Application for plugging approved 06/29/1981
Plugging commenced 06/29/1981
Plugging completed 06/29/1981

Reason for abandonment of well or producing formation
Dry Hole
If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Duane Rankin
Producing formation Depth to top Bottom Total Depth of Well 3397'
Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	286'	8-5/8"	286'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

95 sks com., 2% gel, 3% c.c.:
40 sks @ 450'
30 sks @ 290'
10 sks @ 40' & solid bridge
10 sks rathole
5 sks waterwell,
plug down 8:15 AM, 6/29/81 by Howco

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Allen Drilling Company
P.O. Box 1389, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARTON, ss.
Gary Christopher (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Gary Christopher
P.O. Box 1389, Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of July, 1981

My commission expires



Ruth Brack
RECEIVED
STATE CORPORATION COMMISSION
Notary Public.

1111 - 91981
CONSERVATION DIVISION
Wichita, Kansas
7-9-1981

DRILLER'S WELL LOG

DATE COMMENCED: 06/24/81
DATE COMPLETED: 06/29/81

Tiverton Petroleum, Inc.
RINGWALD No. 1
SE SW NW
Sec. 6, Twp. 19S, Rge 10W,
Rice County, Kansas

ELEVATION: 1772' G.L.
1777' K.B.

FORMATION DATA:

2895 - 2930' Shale
2930 - 3010' Lime
3010 - 3030' Lime, shale
3030 - 3387' Lime
3387 - 3397' Dolomite
3397 - RTD

Heebner 2895'
Toronto 2930'
Brown Lime 3010'
Lansing 3030'
Arbuckle 3387'
RTD 3397'

SURFACE DATA:

Ran 7 jts. 23# new 8-5/8" casing; tally: 279.68';
Set @ 286' w/ 180 sks 60/40 poz. 2% gel, 3% c.c., cement. circ., plug down 8:10 PM, 6/24/81, by Howco

PLUGGING DATA:

95 sks com., 2% gel, 3% cc.:
40 sks @ 450'
30 sks @ 290'
10 sks @ 40' & solid bridge
10 sks rathole
5 sks waterwell,
plug down 8:15 AM, 6/29/81
By Howco

A F F I D A V I T

STATE OF KANSAS)
COUNTY OF BARTON) ss.

RECEIVED
STATE CORPORATION COMMISSION


7.1111 - 91981

CONSERVATION DIVISION
Topeka, Kansas

Gary Christopher, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Gary Christopher

Subscribed and Sworn to before me this 2nd day of July, 1981.


RUTH BRACK
State of Kansas
My Appt. Exp. 9/2/84

Ruth Brack
Notary Public