

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rice County. Sec. 6 Twp. 19 Rge. 10 ~~(E)~~ (W)

Location as "NE/CNW/SW" or footage from lines NE NE SE

Lease Owner Icer Addis

Lease Name Mooney Well No. 4

Office Address Box 27 Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry hole

Date well completed Jan. 28 1959

Application for plugging filed Jan. 29 1959

Application for plugging approved 1959

Plugging commenced 6:00 a. m. Jan. 28 1959

Plugging completed Noon Jan. 28, 1959

Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Gilbert Thoman

Producing formation Depth to top Bottom Total Depth of Well 3378 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	248'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud up to 240', ^{plug at 240'} 1/3 sack of hulls wrapped in sack, 20 sacks of cement, mud up to 40', 10 set plug, 10 sacks of cement. Bridge in rat hole #8 3' below surface, 1 sack of cement.

RECEIVED
STATE CORPORATION COMMISSION
FEB 4 1959
CONSERVATION DIVISION
WICHITA, KANSAS
2-4-1959

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Triangle Drilling, Inc.
Address Box 287 Russell, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Donald D. Vaughan (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Donald D. Vaughan
Box 619 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 29th day of January, 1959

My commission expires April 29, 1961
Dean E. Cooley Notary Public.

PLUGGING
FILE SEC. 6 T. 19 P. 10W
BOOK PAGE 15 LINE 37

WELL LOG

COMPANY Icer Addis
 CONTRACTOR Triangle Drilling, Inc.
 FARM #4 Mooney
 LOCATION NE NE SE of Section 6-19-10W
 Rice County, Kansas
 ELEVATION 1761 KB
 SURFACE PIPE 8 5/8" cemented at 248' with 200 sacks common
 PRODUCTION D & A
 COMMENCED 1-18-59
 COMPLETED 1-28-59

<u>FORMATION</u>	<u>DEPTH</u>
Sandstone	135
Shale and clay	235
Red bed	506
Anhydrite	527
Shale, shells and salt	1230
Shale and limestone	1310
Broken limestone	1580
Broken limestone and shale	1700
Limestone and shale	2593
Limestone	2897
Shale	2982
Limestone	3283
Limestone and shale	3300
Conglomerate	3343
Dolomite	3378

FORMATION TOES

Anhydrite	506 (-1255)
Topeka	2593 (- 832)
Heebner	2863 (-1102)
Toronto	2886 (-1125)
Brown Limestone	2982 (-1221)
Lansing	3002 (-1241)
Base Kansas City	3283 (-1522)
Chert Conglomerate	3300 (-1539)
Arbuckle	3343 (-1582)
RTD	3378 (-1617)

RECEIVED
 STATE CORPORATION COMMISSION

FEB 4 1959

PLUGGING
 FILE SEC. 6 T. 19 R. 10W
 BOOK PAGE 15 LINE 37

A F F I D A V I T

STATE OF KANSAS, COUNTY OF BARTON, SS.

I, Donald D. Vaughan, of the TRIANGLE DRILLING, INC., being first duly sworn on oath, state; That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Donald D. Vaughan
 Donald D. Vaughan

Subscribed and sworn to before me this 30th day of January, 1959.

Dean E. Cooley
 Dean E. Cooley, Notary Public

My commission expires: April 29, 1961.