

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-145-00304-0000

RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1970
CONSERVATION DIVISION
Wichita, Kansas

6-24-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company

Complete Address 915 Union Nat'l Bldg., Wichita, Kansas 67202

Lease Name Fertig Well No. 1

Location NW NW NW Sec. Twp. 15 Rge. 23 (E) (W) 17

County Pawnee Total Depth 4390'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 10:30 A Day 22 Month 6 Year 1970

The above well was plugged as follows:

Total Depth 4390' 8 5/8 csg set at 251' cwc

5 1/2 csg set at 4389' cw 200 sk cmt.

5 1/2 PSTD 4370' With perf. (4234-4342)

Filled 5 1/2 csg W/sd (4200-4370) Dumped 5 sk cmt W/dump bailer (4160-4200)

Cutoff and recovered 3100' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Lesl. Massey
Well Plugging Supervisor

DATE 6/25/70

INV. NO. 2102-W