

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-148. 20010-0600

RECEIVED
STATE CORPORATION COMMISSION

MAY 25 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas.

5-25-1967

Operator's Full Name Messman - Rinehart Oil Company

Complete Address: 1432 Wichita Plaza Wichita, Kansas

Lease Name Frick Well No. 1

Location C. NW SW Sec. 13 Twp. 23 Rge. 17 (E) (W) X

County Pawnee Total Depth 4345

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Murfin Drilling Co.

Address: Wichita, Kansas License No.

Operation Completed: Hour 6 P Day 23 Month 5 Year 1967

The Above well was plugged as follows:

RTD 4345' 8 5/8 csg set at 314' cwc.

Gunned pits, circulated heavy mud, set cementing plug at 500' and displaced 25 sc cem.
thru drill pipe, Heavy mud to 300' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 8 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo A. Massey
Well Plugging Supervisor

DATE 5/26/67

INV. NO. 5286-4