

15-145-01193-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
DEC 17 1969
CONSERVATION DIVISION
Wichita, Kansas

12-17-1969

Operator's Full Name Colorado Oil Company

Complete Address 915 Union National Bldg., Wichita, Kansas 67202

Lease Name Fertig "A" Well No. 7

Location G W/2 W/2 NE Sec. 16 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4310'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 11:15A Day 15 Month 12 Year 1969

The above well was plugged as follows:

Total Depth 4310' 8 5/8 csg set at 276' cwc 200 sk.

5 1/2 csg set at 4308' cw 175 sk cmt.

5 1/2 csg PBTD 4280' and perf. (4247-4260)

Filled 5 1/2 csg W/sd (4200-4280) Dumped 5 sk cmt W/dump bailer. (4160-4200)

Cutoff and recovered 3030' off 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 12/17/69
INV. NO. 1069-11