

15-145-01190-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 17 1969

CONSERVATION DIVISION
Wichita, Kansas

12-17-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company

Complete Address 915 Union National Building Wichita, Kansas 67202

Lease Name Fertig "A" Well No. 4

Location App. E/2 E/2 NE Sec. 16 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4285'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 12:30P Day 15 Month 12 Year 1969

The above well was plugged as follows:

Total Depth 4285' 8 5/8 csg set at 210' cwc 175 sk.

5 1/2 csg set at 4284' cw 175 sk cmt.

5 1/2 PBTB 4273' with top perf. (4238)

Filled 5 1/2 csg W/sd (4200-4273) Dumped 5 sk cmt W/dump bailer. (4160-4200)

Cutoff and recovered 3010' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey
Well Plugging Supervisor

INVOICED
DATE 12/17/69
INV. NO. 1065-40