

15-445-01188-0000

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 17 1969  
CONSERVATION DIVISION  
Wichita, Kansas

12-17-1969

Operator's Full Name Colorado Oil Company

Complete Address 915 Union National Bldg., Wichita, Kansas 67202

Lease Name Fertig "A" Well No. 2

Location App. NE NE NE Sec. 16 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4270'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 5P Day 15 Month 12 Year 1969

The above well was plugged as follows:

Total Depth 4270' 8 5/8 csg set at 217' cwc 175 sk.

5 1/2 csg set at 4268' cw 175 sk cmt.

5 1/2 csg perf. (4260-4268)

Filled 5 1/2 csg W/sd (4200-4270) Dumped 5 sk cmt W/dump bailer. (4160-4200)

Cutoff and recovered 3020' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/500 lbs hulls, plug and 100 sk

Gut.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Mandy  
Well Plugging Supervisor

DATE 12/17/69

INV. NO. 1063-11