

15-145-01186-0000

Form CP-3
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

SEP 29 1967

9-29-1967

CONSERVATION DIVISION
STATE CORPORATION COMMISSION

Operator's Full Name Santa Fe Pipe & Supply, Inc.

Complete Address: P. O. Box 562 Great Band, Kansas

Lease Name Fergus "B" Well No. 2

Location NE NE SW Sec. 16 Twp. 23 Rge. 17 (E) X (W) X

County Pawnee Total Depth 4350'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Co. Tools

Address: License No. 574

Operation Completed: Hour 2: P Day 27 Month 9 Year 1967

The Above well was plugged as follows:

Total Depth 4350' 8 5/8 csg set at 200' cwc 200 sc.

5 1/2 csg set at 4348' cw 150 sc cement.

PB 4344 and perf. (4243-48)

Filled with sand to 4200' and dumped 5 sc cement with dump bailer.

Recov. 2800' of 5 1/2 csg.

Squeezed 8 5/8 csg with 20 sc gel and 80 sc cement and shutin.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: R. W. F. Massey
Well Plugging Supervisor

DATE 9/29/67

INV. NO. 6407-W