

15-145-00864-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 13 1970  
CONSERVATION DIVISION  
Wichita, Kansas

4-13-1970

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Shallow - Water Refining Company

Complete Address 1500 Vickers KSB & T Bldg., Wichita, Kansas 67202

Lease Name Fergus "A" Well No. 4

Location SE SE NW Sec. 16 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4338

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 4P Day 10 Month 4 Year 1970

The above well was plugged as follows:

Total Depth 4338' 8 5/8 csg set at 236' cwc 200 sk.

5 1/2 csg set at 4336' cw 175 sk cmt.

5 1/2 csg FBTD 4315 with top perf. (4231)

Filled 5 1/2 csg W/sd (4200-4315) Dumped 5 sk cmt W/dump bailer. (4160-4200)

Cutoff and recovered 3378' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

with 6% total gel.

I hereby certify that the above well was plugged as herein stated.

Signed: Red F. Mansur  
Well Plugging Supervisor

INVOICED

DATE 4/13/70

INV. NO. 1712-W