

15-145-60863-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 28 1969
CONSERVATION DIVISION
Wichita, Kansas

2-28-1969

J. P. Roberts
Administrator
300 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Shallow Water Refining Company

Complete Address: 1500 Wichita Plaza Wichita, Kansas 67202

Lease Name Fergus "A" Well No. 3

Location NE NE NW Sec. 16 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4390

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 582 Chase, Kansas License No. 436

Operation Completed: Hour 4:30P Day 26 Month 2 Year 1969

The Above well was plugged as follows:

Total Depth 4390' 8 5/8 csg set at 225' cwc 200 sk.

5 1/2 csg set at 4389' cw 150 sk cmt.

5 1/2 csg PBTD 4368' and perf. (4256-64)

Filled 5 1/2 csg W/sd (4250-4368) Dumped 5 sk cmt W/dump bailer. (4210-4250)

Shutoff and recovered 3424' of 5 1/2 csg.

Pumped thru 8 5/8 plug container W/20 sk gel W/5 sk hulls, Plug and 100 sk 50-50poz

Cmt. W/6% total gel. Max. pres. 350 lbs. SI pres. 250 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/28/69

INV. NO. 9395-W

Signed: Ray J. Messer
Well Plugging Supervisor