

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 13 1970

CONSERVATION DIVISION
Wichita, Kansas

4-13-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Shallow Water Refining Company 15-145-00457-0001

Complete Address 1500 Vickers-KSB & T Bldg., Wichita, Kansas 67202

Lease Name Fergus "A" Well No. 1

Location NW NW NW Sec. 16 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4645

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 3P Day 10 Month 4 Year 1970

The above well was plugged as follows:

Total Depth 4645' 8 5/8 csg set at 229' cwc 200 sk.

5 1/2 csg set at 4396' cw 150 sk cmt.

5 1/2 csg PBTD 4370' with top perf. (4275)

Filled 5 1/2 csg W/sd (4200-4370) dumped 5 sk cmt W/dump bailer. (4160-4200)

Cutoff and recovered 3316' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls - plug and 100 sk

50-50 poz cmt W/6% total gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 4/13/70
INV. NO. 1711-W