

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

15-145-00206:0001

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 17 1969  
CONSERVATION DIVISION  
Wichita, Kansas  
12-17-1969

Operator's Full Name Colorado Oil Company  
Complete Address 915 Union National Bldg., Wichita, Kansas 67202  
Lease Name Fertig "A" Well No. 1  
Location NW NW NE Sec. 16 Twp. 23 Rge. (E) (W) 17  
County Pawnee Total Depth 4282  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Knight Casing Pulling Co.  
Address Box 405 Chase, Kansas License No. 436  
Operation Completed: Hour 1:30P Day 15 Month 12 Year 1969

The above well was plugged as follows:

Total Depth 4282' 8 5/8 csg set at 275' cwc 175 sk.

5 1/2 csg set at 4272' cw 175 sk.

Filled 5 1/2 csg W/sd (4200-4282) Dumped 5 sk cmt W/dump bailer. (4160-4200)

Cutoff and recovered 3000' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/500 lbs hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey  
Well Plugging Supervisor

DATE

12/17/69

INV. NO.

1062-4