

15.009.15594.0000

Form CP-3
Rev. 6-26-62

40
KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 1 1965

CONSERVATION DIVISION
Wichita, Kansas

3-1-1965

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Glickman Oil Company

Complete Address: 702 S. St. Francis, Wichita, Kansas

Lease Name P. Scheufler Well No. # 4

Location NW SW NW Sec. 24 Twp. 20 Rge. 12 (E) (W)W

County Barton Total Depth 3372

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Barnes & Sons Pipe Pulling Company

Address: 1216 N. Lincoln, Russell, Kansas license No. # 9

Operation Completed: Hour 2:30PM Day 24 Month 2 Year 1965

The Above well was plugged as follows:

9 5/8" 239' Cwc. plug 3210'. Perf. 2973.'

Set bottom plug @ 2960' & dumped 5 sax cement with dump bailer. Pulled
pipe. Mudded hole to 235'; set rock bridge, 4 sax cement with dump bailer;
let set over-nite, Bailed hole dry: displaced 25 sax cement. Mud to 35';
set rock bridge & displaced 10 sax cement, cementing to base of cellar,

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *John Truman*
Well Plugging Supervisor

DATE 3/1/65

INV. NO. 741-W