

15.009.15602.0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 22 1977 12-22-1977

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Phillips Petroleum Company

Complete Address 7th Floor Frank Phillips Bldg., Bartlesville, Okls. 74004

Lease Name York Marchand Well No. 3

Location C E/2 E/2 NE Sec. 24 Twp. 20 Rge. 12 XX (W) X

County Barton Total Depth 3348
3384

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelse Casing Pulling

Address Box 176 Chase Kansas 67524 License No. 683

Operation Completed: Hour 3:15 PM Day 19 Month 12 Year 1977

The above well was plugged as follows:

Pumped in 25 sx cement at 3347' Pumped in 13 sx of mud gel
at 1630' Recovered 1843' of 5 1/2" casing.
Ran 335' of 2" tubing and pumped in 35 sx cement
Circ cement at 45' with 15 sx cement.
3313' of 5 1/2" casing cemented with 125 sx cement.
285' of 8 5/8" surface casing cement circ,

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Dwan H. Rankin
Well Plugging Supervisor

DATE 12-22-77

INV. NO. 6444-W