

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

R

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 009 - 15593.0000 (of this well)

Operator's Full Name Icer Addis

Complete Address Drawer 3038 Wichita, Kansas 67208

Lease Name Pete Scheufler Well No. 3

Location 110' S N/2 N/2 NW/4 Sec. 24 Twp. 20 Rge. 12 (W)X (W)X

County Barton Total Depth 3339'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well X D & A _____

Other well as hereafter indicated This well was used as A SWD when quit producing.

Plugging Contractor Glenns Casing Pulling, Inc.

Address Box 413 Ellinwood, Kansas 67526 License No. 832

Operation Completed: Hour 1:15 Day 31 Month 8 Year 1979

The above well was plugged as follows:

Sanded back to 3270' and 6 sx cement with dump bailer.

Squeezed thru 10 3/4" surface casing with 3 sx hulls,

10 sx mud gel, 1 sx hulls, and 175 sx cement.

Max. pres 300#. Shut in pres. 200#.

Recovered 499' of 6" casing.

3314' of 7" casing cemented with 250 sx cement.

245' of 10 3/4" surface casing cement circ.

9-4-1979
RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas
SEP - 4 1979

INVOICED

Hereby certify that the above well was plugged as herein stated.

DATE 9-6-79

Signed: Duane Rankin
Well Plugging Supervisor

INV. NO. 0354 W