

15-145. 00141-0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Pawnee SEC. 15 TWP. 23s RGE. 17w E/W
 Location as in quarters or footage from lines:
NW NW NE

Locate Well
 correctly on above
 Section Platt.

Lease Owner W.L. Kirkman, Inc.
 Lease Name Slepake #1 Well No. _____
 Office Address P.O. Box 195, Pratt, Kansas 67124
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 3/31/83
 Plugging completed 4/7/83
 Reason for abandonment of well or producing formation _____

Depleted
 Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Steve Durrant
 Producing formation _____ Depth to top _____ bottom T.D. 4459'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	345'	none
				5 1/2"	4340'	779.23'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Sanded bottom to 4125' & dumped 5 sacks cement, Pipe parted. Pulled 23
joints. Pumped well with 2 hulls, 15 gel, 70 cement, 5 gel, plug, &
100 sacks 50/50 poz, 2% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
 (Address)

SUBSCRIBED AND SWORN TO before me this 8th day of April, 19 83

My Commission expires: 

Irene Hoover
 Notary Public.
 STATE CORPORATION COMMISSION

4-11-1983
 APR 11 1983

15-145-00141-0000

15-23-17W

SOHIO PETROLEUM

#1 PEARL SLEPAKE

NW NW NE ✓

Contr. MUSGROVE PETROLEUM

PAWNEE

County

E 2100 rb Comm. Comp. 9-21-56 IP 1,250,000 CFG

Tops	Depth	Datum
ANH	1115	985
HEEB	3641	-1541
DOUG	3669	-1569
LANS	3761	-1661
CONG SH	4158	-2058
CONG CH	4176	-2076
MISS	4247	-2147
MSNR	4274	-2174
VIO	4303	-2203
STMP	4405	-2305
ARB	4440	-2340
TD	4460	-2360

Casing DST 4164-4204/1 HR, G/10",
 8" 345 2930 MCFG: 2310 MCFG/10"
 5" 4340 285' GCM, BHP 1440#
 DST 4249-93/1 HR, 125' SL GCM, BHP 6300#
 PERF 4275-78: 4285-88: SQZ: CO 4300: RE
 PERF 4275-78, 10 GWPH: PB 4272: PERF
 4263-70, 4 GWPH, SO: PB: PERF 4248-52, 3
 GWPH/3 HRS: PB 4240: PERF 4222-28, 1 1/2
 GWPH/8 HRS: PB 4218: PERF 4210-14: 4200-
 10: ACID 500, 2 3/4 BFPH/3 HRS, SC 0: PB
 4197: PERF 4188-94, 1/2 BAILER WTR: PERF
 24/4174-80: ACID 250: FRAC: PERF 4184-92:
 PKR 4181: ACID 250,
 Garfield 2,410,000 CFG

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

↑ X
X
X

*casing
rec.*

*casing
left*

RECEIVED
STATE COMMISSION

FEB 7 1983

WICHITA, KANSAS

15-145-00141-0000

SOHIO PETROLEUM #1 PEARL SLEPAKE 15-23-17W
NW NW NE ✓

Contr. MUSGROVE PETROLEUM PAWNEE County

E2100 rb Comm. Comp. 9-21-56 IP 1,250,000 CFG

Tops	Depth	Datum
ANH	1115	985
HEEB	3641	-1541
DOUG	3669	-1569
LANS	3761	-1661
CONG SH	4158	-2058
CONG CH	4176	-2076
MISS	4247	-2147
MSNR	4274	-2174
VIO	4303	-2203
SIMP	4405	-2305
ARB	4440	-2340
TD	4460	-2360

Casing DST 4164-4204/1 HR, G/10",
8" 345 2930 MCFG: 2310 MCFG/10"
5" 4340 285' GCM, BHP 1440#
DST 4249-93/1 HR, 125' SL GCM, BHP 6300#
PERF 4275-78: 4285-88: SQZ: CO 4300: RE
PERF 4275-78, 10 GWPB: PB 4272: PERF
4263-70, 4 GWPB, SO: PB: PERF 4248-52, 3
GWPB/3 HRS: PB 4240: PERF 4222-28, 1 1/2
GWPB/8 HRS: PB 4218: PERF 4210-14: 4200-
10: ACID 500, 2 3/4 BFPB/3 HRS, SC 0: PB
4197: PERF 4188-94, 1/2 BAILER WTR: PERF
24/4174-80: ACID 250: FRAC: PERF 4184-92:
PKR 4181: ACID 250,

Garfield

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

RECEIVED
STATE CORPORATION COMMISSION

APR 25 1983

CONSERVATION DIVISION
Wichita, Kansas