

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

15-145-08437-0001
RECEIVED Form CP-4 Rev. 12-15-80
STATE CORPORATION COMMISSION
SEP 30 1982
CONSERVATION DIVISION
Wichita, Kansas
9-30-1982

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Pawnee SEC. 11 TWP. 23 RGE. 17 E/W
Location as in quarters or footage from lines:
SW SW NW

Locate Well correctly on above Section Platt.

Lease Owner Sterling Drilling Company
Lease Name Van Vleet Well No. 1
Office Address Box 129 Sterling, Kansas 67579
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 9-23-82
Plugging completed 9-27-82
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J.H. Metz
Producing formation _____ Depth to top _____ bottom _____ T.D. 4419'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				10-3/4"	705'	none
				4-1/2"	4410'	1924'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Pumped bottom with 4 sacks hulls, 10 gel, 35 sacks cement and 4-1/2" plug. Plug @1930'. Shot casing @1921' and pulled a total of 45 joints of 4-1/2" casing. Pumped in 3 hulls and 6 gel, developed hole in casing, had welder weld plates on casing, pumped in 3 hulls, 15 gel, 70 cement, 1 hull, 10 gel, released plug and displaced with 150 sacks cement, 50/50 pos, 4% gel, 3% cc.
Plugging Complete.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 1982



Irene Hoover
Notary Public.

My Commission expires: