

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Pawnee County, Sec. 11 Twp. 23 Rge. 17 (X) W (W)

Location as "NE/CNWSW%" or footage from lines SW SW SE

Lease Owner Woodman & Jannitti Drilling Co.

Lease Name Paramore Well No. 1

Office Address P. O. Box 387, Hoisington, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed November 20, 1956

Application for plugging filed November 20, 1956

Application for plugging approved November 20, 1956


Plugging commenced November 20, 1956

Plugging completed November 20, 1956

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well John Roberts

Producing formation Depth to top Bottom Total Depth of Well 4285' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	256'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud. Push B<sup>ottom</sup> plug to 250' and bridge hole & 20 sacks cement. Top plug down 35', 1/3 sack hulls & 10 cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Woodman & Jannitti Drilling Co.

Address P. O. Box 387, Hoisington, Kansas

STATE OF Kansas, COUNTY OF Sedgwick  
K. T. Woodman (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) K. T. Woodman

(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of November, 1956

My commission expires 11-30-59

Lucille S. Hoisington  
Notary Public.

PLUGGING  
FILE SEC 11 T 23 R 17 W  
BOOK PAGE 118 L F E 23

RECEIVED  
11-26-1956  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
WICHITA, KANSAS

D R I L L I N G   L O G

15-145-66147-0000

Company: Woodman & Iannitti Drilling Co., and  
Brown and Fortier

Lease: Paramore

Well: #1 Paramore SW SW SE 11-23-17W, Pawnee Co., Kansas

Contractor: Woodman & Iannitti Drilling Co.  
P. O. Box 387, Hoisington, Kansas

Date Comm: 11-6-56  
Date Compl: 11-20-56

T. D. 4285'

Casing: 256' 8 5/8" surface casing

Figures Indicate the Bottom of Formation

0-115	Sand	3380	Shale & Shells
140	Shale & Shells	3460	Lime & Shale
256	Shale & Shells	3555	Lime and Shale
317	Shale & Shells	3590	Lime & Shale
323	Shale & Sand	3635	Shale & Lime
350	Shale & Shells	3647	Shale & Lime
475	Shale & Shells	3674	Shale & Lime
555	Red Bed & Shale	3725	Lime
625	Dakota Sand	3745	Lime
950	Red Bed & Shale	3790	Lime
1080	Red & Shale	3865	Lime
1115	Anhydrite	3935	Lime
1250	Red Bed, Shale & Shells	3990	Lime
1535	Red Bed, Shale & Shells	4035	Lime
1600	Shale & Salt	4054	Shale & Lime
1745	Shale & Shells	4096	Lime, Shale, Sand & Chert
1755	Brown Lime	4115	Lime & Shale
1910	Shale & Lime	4150	Lime-Shale-Chert
1970	Lime	4170	Chert
2080	Lime	4205	Lime
2220	Brown Lime & Shale	4221	Lime & Shale
2330	Lime	4235	Simpson
2410	Lime	4280	Arb.
2445	Lime & Shale	4285	Total Depth
2475	Florence Flint		
2485	Shale & Lime		
2605	Lime Shale		
2705	Lime & Shale		
2810	Lime & Shale		
2940	Shale & Shells		
3100	Shale & Shells		
3230	Shale & Shells		
3355	Shale & Shells		

<b>PLUGGING</b>	
FILE NO. 11 T. 23 R. 17W	Well No. Kansas
BOOK PAGE 118 LINE 22	

**RECEIVED**  
STATE CORPORATION COMMISSION

NOV 26 1956  
CONSERVATION DIVISION  
Well No. Kansas

15-145-00147-0000

GEOLOGICAL TOPS

Elevation	2087	RB
Heebner	3558	-1471
Brown Lime	3665	-1578
Lansing	3674	-1587
Conglomerate	4079	-1992
Viola	4124	-2057
Simpson	4203	-2116
Arbuckle	4231	-2144
Total Depth	4285	-2198

I certify the above to be a true and correct copy of the Driller's Log and Geological Tops, to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING COMPANY

BY

*K. T. Woodman*

K. T. WOODMAN

PLUGGING

FILE SEC 11 T 23 R 17W  
BOOK PAGE 118 LINE 23