


15-145-20347-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Pawnee County, Sec. 13 Twp. 23 Rge. 17 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines _____
C of SE SW
Lease Owner National Oil Company
Lease Name Van Vleet #1 Well No. _____
Office Address Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9/12/78 _____ 19____
Plugging completed 10/9/78 _____ 19____
Reason for abandonment of well or producing formation
depeltd.
If a producing well is abandoned, date of last production _____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4260
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	300	none
				4 1/2"	4231	3120'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Squeezed bottom hole with 35 sacks cement, pumped plug to 3900'. Shot pipe at 3440', 3245'
and 3105', worked pipe loose and pulled 93 joints. Squeezed hole with 3 sacks hulls, 25 sacks
gel, released plug and displaced with 150 sacks 50-50 pozmix 2% gel.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

OCT 16 1978 10-16-1978

(If additional description is necessary, use BACK of _____)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS


STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of October, 19 78

Margaret Orndorff
Notary Public.

My commission expires _____



K. T. WOODMAN
RES. PHONE 733-0418
OFF. PHONE 265-7650
WICHITA, KANSAS

D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

WOODMAN & IANNITTI OIL COMPANY

Rotary Drilling Contractors

1008 UNION NATIONAL BUILDING
WICHITA, KANSAS 67202

15-145-20347-0080

October 3, 1974

Company:	National Oil Company
Farm;	#1 Van Vleet
Location;	C SW
Section;	13-23-17W
County;	Pawnee
Contractor;	Woodman & Iannitti Drilling Co.
Comm;	September 22, 1974
Compl;	October 3, 1974
Total Depth;	4260
Casing;	8 5/8" @ 299.38 w/250 sx. 4 1/2" @ 4231 w/150 sx.

Figures Indicate Bottom Of Formation:

30	Clay
50	Sand
140	Clay & Sand Streak
300	Shale & Sand Streaks
440	Shale
560	Red Bed & Shale
595	Sand
1085	Shale & Red Bed
1090	Anhy
1108	Anhy
1670	Shale & Shells
2165	Lime
2515	Lime
2990	Lime & Shale
3240	Lime & Shale
3350	Lime
3710	Lime & Shale
3980	Lime
4115	Lime
4180	Lime
4240	Lime
4260	Lime

RECEIVED
STATE CORPORATION COMMISSION

AUG 07 1978

CONSERVATION DIVISION
Wichita, Kansas

I certify the above to be a true and correct copy of the driller's log to the best of my knowledge and belief.

Woodman & Iannitti Drilling Co.

K. T. Woodman
K. T. Woodman