


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Pawnee County. Sec. 16 Twp. 23S Rge. 17W (E)____(W)
Location as "NE/CNW/SW" or footage from lines NE NW SE
Lease Owner Shallow Water Refining Company
Lease Name Fergus "C" Well No. 2
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 2/27/67 _____ 19____
Plugging completed 3/ 2/67 _____ 19____
Reason for abandonment of well or producing formation depleted.

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4356 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	229	none
				5 1/2	4354	2723.48

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom. Ran sand to 4200', dumped 5 sacks of cement. Cleaned cellar, rigged up on 5 1/2", had trouble with National braden head. Had 21" tension. Loaded hole, shot pipe at 3106', 3016', 2925', 2815', 2715'. Worked pipe loose and pulled 30 joints. Pulled 52 joints of 5 1/2", pipe was breaking hard. Cleared floor, loaded junk rack, tried to clean out cellar. Kept caving in. Cleaned cellar, had welder cut off braden head. Weld on 8 5/8 slip collar. Hook up pump, pumped 25 sacks gel mud and 80 sacks of cement. Racked pump and unit.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of March, 19 67

My commission expires February 15, 1971
Margaret Melcher
Notary Public.

15-445-01194-0000

DRILLER'S LOG

COMPANY: WESTPAN HYDROCARBON COMPANY

LOCATION: **NE NW**
N/2 N/2 SE
SECTION 16-23S-17W
PAWNEE COUNTY, KANSAS

CONTRACTOR: HILTON DRILLING COMPANY, INC.

FARM NAME: FERGUS "C" No. 2

ELEVATION: 2101' D. F.

COMMENCED: APRIL 16, 1957

CASING USED: 8-5/8" @ 219' W/200 sxs.
5-1/2" @ 4368' W/150 Sxs.

COMPLETED: APRIL 30, 1957

CLAY, SAND AND GRAVEL	40
CLAY	50
SAND	70
SHALE AND SAND	150
SAND	165
SHALE	219
RED BED AND SHALE	465
RED BED AND SAND	605
SAND	670
RED BED	1135
ANHYDRITE	1165
SHALE AND SHELLS	1265
SHALE, SHELLS AND SALT	1640
SHALE AND SHELLS	2010
LIME AND SHALE	2230
LIME	2335
LIME AND SHALE	2780
LIME	3355
LIME AND SHALE	3716
SHALE AND LIME	3787
SHALE	3800
LIME	3867
LIME AND SHALE	4159
LIME AND CONGLOMERATE	4225
CHERT AND SHALE	4286
CHERT AND LIME	4297
CHERT, LIME, AND SAND	4352
SHALE	4361
LIME AND CHERT	4370
TOTAL DEPTH	4370

RECEIVED
STATE CORPORATION COMMISSION
FEB 18 1957
CONSERVATION DIVISION
WICHITA, KANSAS

STATE OF KANSAS)
) SS.
COUNTY OF BARTON)

I, THE UNDERSIGNED, BEING DULY SWORN ON OATH, STATE THAT THE ABOVE STATEMENT AND LOG ARE TRUE AND A CORRECT RECORD AND LOG OF THE WELL DRILLED AT THE LOCATION ABOVE-DESCRIBED.

HILTON DRILLING COMPANY, INC.

Henry Peacock
HENRY PEACOCK, SECRETARY

SUBSCRIBED AND SWORN TO BEFORE ME THIS 7TH DAY OF MAY, 1957.

Mildred Hobbie
NOTARY PUBLIC
MILDRED HOBBIIE
MY COMMISSION EXPIRES MARCH 6, 1958