

15-145-01191-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

R
WELL PLUGGING RECORD

Pawnee County, Sec. 16 Twp. 23S Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines SW SW NE

Lease Owner Peel-Hardman Oil Operators

Lease Name Fertig Well No. 5

Office Address R. R. #3, Box 144B, Wichita 20, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil Well

Date well completed Sept. 3, 1955

Application for plugging filed July 17, 1959

Application for plugging approved July 22, 1959


Plugging commenced Sept. 23, 1959

Plugging completed Sept. 29, 1959

Reason for abandonment of well or producing formation No longer a commercial producer

If a producing well is abandoned, date of last production 3-20 19 59

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot

Producing formation Penn.-Miss. Depth to top 4250 Bottom 4310 Total Depth of Well 4310 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	192	8 5/8"	192	None
		0	4299	5 1/2"	4299	3/28

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole from 4310 to 4220'
Dumped 5 sacks cement and pumped 37 barrels of mud and 60 sacks of cement into surface nine - checked hole - cement was down 85'.
Set 10' rock bridge - dumped 5 sacks cement.

10-16-1959
RECEIVED
STATE CORPORATION COMMISSION
OCT 16 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R & D Casing Pulling Company License #236
Address Box 569, Ellinwood, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
William Herbert (employee of owner) of (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *William Herbert*

R. R. #3, Box 144B, Wichita 20, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of October, 19 59

Marion M. Herbert
Notary Public.

My commission expires March 4, 1962.



15-145-01191-0000

DRILLERS' LOG

Company: Peel-Hardman Oil Producers

SW SW NE
Sec. 16, Twp. 23S, Rge. 17W,

Farm Name: Fertig Well No. 5

County: Pawnee,
Kansas

Total Depth: 4300'

Comm: 8-18-55 Comp: 8-31-55

Contractor: Glenn W. Peel

Elevation:

Casing: 8 5/8" 192' cem.
5 1/2" 4299' cem.

Production:

Figures below indicate bottoms of formations:

Sand	0 -	99
Shale, shells, red bed		750
Shale, shells		1130
Anhydrite		1165
Shale and shells		2000
Shale and lime		2425
Lime		2625
Shale and shells		2765
Lime and shells		2900
Shale and shells		3175
Lime		3960
Lime and shale		4060
Lime		4285
Lime and sand		4300
Total Depth		4300

This is to certify that the above information is to the best of our knowledge, true and correct.

GLENN W. PEEL

BY: *Glenn W. Peel*

SUBSCRIBED AND SWORN to before me this 7th day of September, 1955

My commission expires: June 4, 1959

Marion M. Herbert
Notary Public

RECEIVED
STATE CORPORATION COMMISSION

JUL 18 1959

CONC... DIVISION
...sas

PLUGGING
FILE SEC 16 T 23 R 17 W
BOOK PAGE 52 LINE 4