

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavits
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 16 Twp. 23 Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines 440' SNL, 440' WEL
Lease Owner Colorado Oil Company
Lease Name Fertig "A" Well No. 2
Office Address 915 Union National Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed March 25 1955
Application for plugging filed October 27 1969
Application for plugging approved October 28 1969
Plugging commenced December 5 1969
Plugging completed December 15 1969
Reason for abandonment of well or producing formation Depleted

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production September 1969
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Conglomerate Chert Depth to top 4246 Bottom Total Depth of Well 4270 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	217'	None
				5-1/2"	4269'	3031'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 4200', demped 5 sacks of cement.
Loaded hole, shot pipe at 3207', 3035', worked pipe loose and pulled 94 joints. Halliburton pumped 5 sacks of hulls, 20 sacks of gel and 100 sacks of cement to plug well.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
DEC 24 1969
CONSERVATION DIVISION
Wichita, Kansas

12-24-1969

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co., Inc.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bill K. Henrichs (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill K. Henrichs
915 Union Natl. Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 1969

My commission expires February 19, 1973

Betty J. McElwain
Notary Public.

15-145-01188-0000

DRILLERS' LOG

Company: Peol-Hordman Oil Producers

440' from RL; 440' from EL; EA/4
Sec. 16, Twp. 23S, Rge. 17W,

Farm Name: Cortig Cell No. 2

County: Pawnee,
Kansas

Total Depth: 4270'

Conn: 3-12-55 Comp: 3-25-55

Elevation:

Contractor: Glenn W. Peol

Production:

Casing: 5 5/8" 217' con.
5 1/2" 4253' con.

Figures below indicate bottoms of formations:

Sand, surface clay	0 -	60
Sand and shale		217
Shale		330
Red bed and shells		975
Shale		2070
Shale and lime streaks		2220
Lime and shale		2410
Shale and lime streaks		2705
Lime and shale		2920
Shale		3045
Shale and lime		3160
Lime		3230
Lime and shale		3415
Lime		3675
Lime and shale		3915
Lime		4270
Total Depth		4270

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1969
CONSERVATION DIVISION
Wichita, Kansas

This is to certify that the above information is to the best of our knowledge, true and correct.

GLENN W. PEOL

BY: *Wm Herbert*

SUBSCRIBED AND SWORN to before me this 29th day of March, 1955.

My commission expires: June 6, 1955

Marian M. Herbert
Notary Public