

15-145-01186-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

PAWNEE County, Sec. 16 Twp. 23S Rge. 17W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner SANTA-FE PIPE & SUPPLY, INC.

Lease Name FERGUS "B" Well No. 2

Office Address BOX 562, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) OIL

Date well completed _____ 19__

Application for plugging filed JULY 18 19 67

Application for plugging approved JULY 20 19 67


Plugging commenced JULY 28 19 67

Plugging completed SEPTEMBER 27 19 67

Reason for abandonment of well or producing formation DEPLETED

If a producing well is abandoned, date of last production _____ 19__

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well MR. LEO MASSEY

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4350 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	200	NONE
				5 1/2	4348	2839

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4350 - 4334 - PLUG
 4334 - 4240 - SAND
 4240 - 4200 - 5 SACKS CEMENT
 4200 - 240 - PUMPED 20 SACKS JEL MUD
 240 - BASE - PUMPED 80 SACKS CEMENT

RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1967

10-12-1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address BOX 562, GREAT BEND, KANSAS

STATE OF KANSAS COUNTY OF BARTON, ss.
T.L. NUTT (XXXXXXXXXX)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *T.L. Nutt*

BOX 562, GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN TO before me this 11TH day of OCTOBER, 19 67

My commission expires JULY 31, 1970

Mary M. Guernier
Notary Public.

15-145-01186-0000

COPY


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- HILTON DRILLING CO.
Ferm- Fergus "B" No. 2

SEC. 16 T. 23 R. 17W
NE NE SW

Total Depth. 4350'
Comm. 6-27-55 Comp. 7-10-55
Shot or Treated.
Contractor.
Issued. 7-28-56

County Prownee
KANSAS



Elevation. 2101'

Production. 135 BOPD

Figures indicate Bottom of Formations.

sand	40
sand, clay	100
shale	220
shale	385
red rock, shale	605
sand	663
red rock	1120
anhydrite	1150
shale shells, salt	1810
sand, shells	1960
shale, lime	2070
lime	2440
shale, lime	2580
lime	2690
shale, lime	3335
lime	3706
shale, lime	3772
shale	3782
lime	4191
shale, lime	4237
shale, lime chert	4248
shale, chert	4262
shale	4271
shale, lime, chert	4286
lime, chert	4338
shale, chert	4350
Total Depth	

Tops: Scout	
Lansing	3790
Conglomerate	4215
Ch. Conglomerate	4231
Mississippi	4271
Misner	4321

RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1967

CONSERVATION DIVISION
Wichita, Kansas