


15445-00864-0000  
 APR 23 1970

STATE OF KANSAS  
 STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely  
 Make Required Affidavit  
 Mail or Deliver Report to:  
 Conservation Division  
 State Corporation Commission  
 212 No. Market  
 Wichita, Kansas 67202

WELL PLUGGING RECORD



Locate well correctly on above  
 Section Plat

Pawnee County, Sec. 16 Twp. 23 Rge. 17 (E) W (W)  
 Location as "NE/CNWxSWx" or footage from lines SE SE NW  
 Lease Owner Shallow Water Refining Company  
 Lease Name Fergus A#4 Well No. \_\_\_\_\_  
 Office Address Kansas City, Missouri  
 Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
 Date well completed \_\_\_\_\_ 19\_\_\_\_  
 Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
 Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
 Plugging commenced 4/2/70 \_\_\_\_\_ 19\_\_\_\_  
 Plugging completed 4/10/70 \_\_\_\_\_ 19\_\_\_\_  
 Reason for abandonment of well or producing formation depleted.  
 If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
 Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Massey  
 Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4338 Feet  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	236	none
				5 1/2	4336'	3359'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked bottom, ran sand to 4200' and dumped 5 sacks of cement.  
 Loaded hole, shot pipe at 3382', worked pipe loose and pulled  
 103 joints. Allied pumped 5 sacks hulls, 20 sacks gel and 100  
 sacks of cement to plug well.

PLUGGING COMPLETE.


RECEIVED  
 STATE CORPORATION COMMISSION  
 APR 30 1970  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 4-30-1970

(If additional description is necessary, use BACK of this sheet)  
 Name of Plugging Contractor KNIGHT CASING PULLING CO., INC.  
 Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
CHASE, KANSAS  
 (Address)

Subscribed and sworn to before me this 13th day of April, 1970



Margaret D. Melcher  
 Notary Public.

My commission expires 2/15/71

REC'D APR 23 1970

15-145-00864-000

DRILLER'S LOG

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas

COMPANY: Westpan Hydrocarbon Company  
CONTRACTOR: Hilton Drilling Company, Inc.  
FARM NAME: Fergus "A" No. 4  
COMMENCED: September 10, 1955  
COMPLETED: September 25, 1955

LOCATION: SE SE NW  
Section 16-23S-17W  
Pawnee County, Kansas  
ELEVATION: 2100 D.F.

Casing Used: 8-5/8" @ 236' with 200 sx.  
5-1/2" @ 4336' with 150 sx.

Sand, Shale and Shells	236
Shale and Shells	390
Red Bed and Shells	450
Shale and Shells	475
Shells and Lime	590
Sand	685
Red Bed and Shells	825
Shale and Red Bed	1130
Anhydrite	1160
Shale, Shells and Salt	1310
Shale and Shells	1860
Shale and Lime	2335
Lime	2625
Shale and Lime	3285
Lime	3460
Shale and Lime	3485
Lime	3665
Shale and Lime	3720
Lime	4274
Sand, Chert and Lime	4322
Lime	4338
Total Depth	4338

STATE OF KANSAS )  
                  ) SS  
COUNTY OF BARTON )

I, the undersigned, being duly sworn on oath, state that the above statement and log are true and a correct record and log of the well drilled at the location above-described.

HILTON DRILLING COMPANY, INC.

Henry Peacock, Secretary

Subscribed and sworn to before me this 26th day of September, 1955.

My commission expires January 26, 1959

Carmen Reinhardt Leiker, Notary Public