

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 16 Twp 23 Rge. (E) 17 (W)
Location as "NE/CNW/SW" or footage from lines NW NW NE
Lease Owner Colorado Oil Company
Lease Name Fertig "A" Well No. 1
Office Address 915 Union Natl. Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed November 15 19 54
Application for plugging filed October 27 19 69
Application for plugging approved October 28 19 69
Plugging commenced December 2 19 69
Plugging completed December 15 19 69
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production September 19 67
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Conglomerate Chert Depth to top 4270 Bottom Total Depth of Well 4282 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	275'	None
				5-1/2"	4272'	2987'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 4200', dumped 5 sacks of cement.
Loaded hole, shot pipe at 3206', 3005' worked pipe loose and
pulled 94 joints. Halliburton pumped 5 sacks of hulls, 20 sacks
of gel and 100 sacks of cement to plug well.

PLUGGING COMPLETE.

RECEIVED 12-24-1969
STATE CORPORATION COMMISSION
DEC 24 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co., Inc.
Address Chas., Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.

Bill K. Henrichs (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill K. Henrichs
915 Union Natl. Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 19 69

My commission expires Feb. 19, 1973

Betty J. McElwain
Betty J. McElwain Notary Public.

WILLIAMS' LOG

Company: Peel-Hardman Oil Producers

LN 15 IE

Farm Name: Fortig Well No. 1

Sec. 16, Twp. 23N, Rge. 17W,

Total Depth: 4232'

County: Pawnee,
Kansas.

Comm: 11-2-54 Comp: 12-13-54

Contractor: Glenn H. Peel

Elevation: 2101 KB

Coring: 3 5/8" 275' con.
3 1/2" 4272' con.

Production:

Figures below indicate bottoms of formations:

Surface clay	0 -	30
Shale		405
Red bed and shells		1040
Shale		1150
Anhydrite		1190
Shale and shells		1360
Shale and lime		2340
Lime		2440
Lime and shale		2520
Lime		2800
Lime and shale		2930
Shale		3260
Lime and shale		3610
Lime		4232
Total Depth		4232

RECEIVED
STATE CORPORATION COMMISSION
OCT 28 1969
CONSERVATION DIVISION
Wichita, Kansas

This is to certify that the above information is to the best of our knowledge, true and correct.

GLENN H. PEEL

BY: Way Herfur

WITNESSED AND SIGNED to before me this 16th day of November, 1954.

My commission expires: June 4, 1955

Marian M. Herbert
Notary Public

Geological Tops:

Brown Lime - - - - - 3800 KB
Conglomerate Shale - 4247 KB
Conglomerate Chert - 4270 KB