

15-145-00187-0000
20

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

PAWNEE County. Sec. 16 Twp. 23S Rge. 17W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW
Lease Owner SANTA-FE PIPE & SUPPLY, INC.
Lease Name FERGUS "B" Well No. 1
Office Address BOX 562, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL
Date well completed _____ 19____
Application for plugging filed JULY 18 1967
Application for plugging approved JULY 20 1967
Plugging commenced JULY 21 1967
Plugging completed SEPTEMBER 27 1967
Reason for abandonment of well or producing formation DEPLETED



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well MR. LEO MASSEY
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4375 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	237	NONE
				5 1/2	4372	2148

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4375 - 4249 - PLUG
4249 - 4225 - SAND
4225 - 4185 - 5 SACKS CEMENT
4185 - 240 - PUMPED 20 SACKS JEL MUD
240 - BASE - PUMPED 80 SACKS CEMENT

10-12-1967
RECEIVED
STATE CORPORATION COMMISSION

OCT 12 1967

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor SANTA-FE PIPE & SUPPLY, INC.
Address BOX 562, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
T.L. NUTT (Employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *T.L. Nutt*
BOX 562, GREAT BEND, KANSAS
(Address)

SUBSCRIBED AND SWORN to before me this 11TH day of OCTOBER, 1967

My commission expires JULY 31, 1970
Mary M. Guenier Notary Public.

15-145-60187-0000

COPY


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- HILTON DRILLING CO., INC. ET AL
Farm- Fergus "B" No. 1

SEC. 16 T. 23 R. 17W
NW SW

Total Depth. 4375'
Comm. 9-10-54 Comp. 9-24-54
Shot or Treated.
Contractor. Hilton Drilg. Co., Inc.
Issued. 4-9-55

County Pawnee KANSAS



Elevation. 2109'

Production. 36 B.

CASING:

8 5/8" 237' w/200 sx cem.
5 1/2" 4372' w/150 sx cem.

Figures indicate Bottom of Formations

sand-gravel	40
sand-claey	100
clay	150
sand-shale-shells	180
shale-shells	238
sand-shale-shells	385
red bed-sand	680
red bed	1040
red bed	1125
Anhydrite	1155
shale-shells	1605
shale-lime	2010
Brown lime-shale	2070
lime	2445
shale-lime	2980
brwon limo-shale	3125
shale-lime	3175
lime	3235
shale-lime	3329
lime	3705
shale-lime	3783
lime	4124
shale-lime	4184
sand-shale-lime	4238
shale-lime-chert	4343
lime-chert	4373 RTD
lime-chert ?	4375
Total Depth	

TOPS: Scout	
Heebner	3674
Brown lime	3779
Lansing	3787
B/Kansas City	4160
Conglomerate chert	4227
Mississippi	4248
Misener	4300
Viola	4334

RECEIVED
STATE CORPORATION COMMISSION

JUL 20 1967

CONSERVATION DIVISION
Wichita, Kansas