


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

See All Information Completely
Re Required Affidavit
If or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 24 Twp. 20 Rge. 12 (X) (W)
Location as "NE/CNW/SW" or footage from lines NE SW SE

Lease Owner Leben Drilling, Inc.
Lease Name ~~XXXXXXXXXX~~ Scheufler Well No. 1
Office Address P. O. Box 486, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 5-11-64 19
Application for plugging filed 5-11-64 19
Application for plugging approved 5-11-64 19
Plugging commenced 5-11-64 19
Plugging completed 5-11-64 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan, Russell, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3415 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	264'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plug with $\frac{1}{2}$ sack hulls and 25 sacks cement at 255'
Top plug at 40' with $\frac{1}{2}$ sack hulls and 10 sacks cement
2 sacks cement in rathole.

5-13-1964
RECEIVED
STATE CORPORATION COMMISSION

MAY 13 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Leben Drilling, Inc.
Address P. O. Box 486, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

Leslie Kite (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Leslie KiteP. O. Box 486, Great Bend, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of May, 1964My commission expires April 1, 1967Ulanda Nichols

Notary Public.

DRILLER'S LOG

COMPANY: Leben Drilling, Inc.
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: SCHEUFLE #1
 LOCATION: NE SW SE Sec. 24-20-12
 BARTON COUNTY, KANSAS
 COMMENCED: 5-4-64
 COMPLETED: 5-11-64

0	125	Sand & Gravel
125	264	Shale & Redbed
264	570	Redbed
570	600	Anhydrite
600	910	Redbed & Shale
910	1115	Shale & Lime
1115	1350	Shale
1350	1570	Lime & Shale
1570	1910	Lime
1910	2500	Shale & Lime
2500	2922	Lime
2922	3155	Lime & Shale
3155	3415	Lime
	<u>3415</u>	<u>Rotary Total Depth - D. & A.</u>

Set 8 5/8" used surface casing @ 264' cemented with 275 sacks Sunset

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Scheufler #1 well, located NE SW SE of Section 24, Township 20, Range 12, Barton County, Kansas, as reflected by the files of Leben Drilling, Inc.

Leslie Kite

Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to before me, a Notary Public, in and for Barton County, Kansas, this 12th day of May, 1964.

Ulanda Nichols

Ulanda Nichols

My Commission Expires
April 1, 1967

RECEIVED
 STATE CORPORATION COMMISSION

MAY 13 1964

CONSERVATION DIVISION
 Wichita, Kansas