


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barton County, Sec. 24 Twp. 20S Rge. 12W (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner Leben, Bankoff, Reed
Lease Name Scheufler Well No. 1
Office Address Box 486, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-21-66 19__
Application for plugging filed 9-21-66 19__
Application for plugging approved 9-21-66 19__
Plugging commenced 9-21-66 19__
Plugging completed 9-21-66 19__
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3410 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	256'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded to 250', set plug, 25 sacks cement through drill pipe
Mudded to 40', 1/2 sk. hulls, set plug, 10 sacks cement
put 2 sacks cement in rathole.

RECEIVED
STATE CORPORATION COMMISSION
SEP 26 1966
CONSERVATION DIVISION
WICHITA, KANSAS
9-26-1966

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Leslie Kite (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leslie Kite
P. O. Box 486, Great Bend, Ks. 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of September, 1966

My commission expires April 1, 1967
Ulanda Nichols
Ulanda Nichols Notary Public.

DRILLER'S LOG

COMPANY: Leben, Bankoff, Reed
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: SCHEUFLER #1
 LOCATION: SE SE SE SEC. 24-20S-12W
 BARTON COUNTY, KANSAS
 COMMENCED: 9-15-66
 COMPLETED: 9-21-66

0	40	Clay, Sand
40	203	Sand
203	256	Shale
256	579	Redbed
579	592	Anhydrite
592	1420	Shale, Shells
1420	1430	Shale, Lime
1430	2200	Lime, Shale
2200	2650	Shale, Lime
2650	2820	Lime, Shale
2820	2975	Lime
2975	3000	Lime, Shale
3000	3095	Shale
3095	3353	Lime
3353	3410	Arbuckle
	<u>3410</u>	<u>RTD - D. & A.</u>

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 20 1966
 CONSERVATION DIVISION
 Wichita, Kansas

Set 8 5/8" used surface casing @ 256' cemented with 275 sacks cement

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Scheufler #1 Well, located SE SE SE of Section 24, Township 20 South, Range 12 West Barton County, Kansas, as reflected by the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 24th day of September, 1966.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1967