


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 9 Twp. 23 Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines SE SE NW  
Lease Owner Colorado Oil Company  
Lease Name Hutchinson "E" Well No. 2  
Office Address 915 Union Natl. Bldg., Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Oil  
Date well completed December 24 1954  
Application for plugging filed December 15 1969  
Application for plugging approved December 16 1969  
Plugging commenced December 19 1969  
Plugging completed January 15 1970  
Reason for abandonment of well or producing formation Depleted

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production December 4 1969  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey  
Producing formation Congl. Chert Depth to top 4200 Bottom Total Depth of Well 4303 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	241	None
				5-1/2"	4359'	2703'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked bottom, ran sand to 3950', dumped 5 sacks of cement.  
Loaded hole, shot pipe at 3283', 3185', 3065', 2975', 2883',  
2779', 2681', worked pipe loose and pulled 83 joints.  
Halliburton pumped 5 sacks hulls, 20 sacks of mud and  
100 sacks of cement to plug well.

PLUGGING COMPLETE

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 27 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co., Inc.  
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Bill K. Henrichs (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill K. Henrichs  
915 Union Natl. Bldg., Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of January, 1970

My commission expires Feb. 19, 1973

Betty J. McElwain  
Betty J. McElwain Notary Public.

15-145-66954-0000

HONAKER DRILG., INC.  
2008 LAKIN  
GREAT BEND, KANSAS

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 16 1969  
CONSERVATION DIVISION  
Wichita, Kansas

DRILLERS LOG

Hutchinson E No. 2  
Loc: SE SE NW  
Sec: 9-23-17W  
Pawnee County, Kansas  
Contractor: Honaker Drilg., Inc.

Elevation: 2083 D.F.  
Comm: 12-6-54  
Comp: 12-18-54  
Total Depth: 4360'  
Casing: 8-5/8" @ 241'  
5-1/2" @ 4359'

0	40	Sand	
40	60	Sand & Gravel.	
60	180	Clay	
180	390	Blue Shale.	8-5/8" casing cemented @ 241'
390	700	Red Bed.	with 200 sacks cement and 4
700	1125	Red Bed & Shale.	sacks calcium chloride
1125	1165	Anhydrite.	
1165	1580	Shale & Shells.	
1580	1660	Salt & Shale.	
1660	1870	Shale & Shells.	
1870	3844	Lime & Shale.	
3844	4357	Lime.	
4357	4360	Lime & Chert.	
4360		Rotary Total Depth	5-1/2" casing cemented @ 4359' with 174 sacks cement.

I certify that this is the true and correct copy of the above log, to the best of my knowledge.

*H. Forbes*

Subscribed and sworn to before me this 20<sup>th</sup> day of December, 1954.

*Ruth D. Fisher*  
Notary Public

My Commission Expires: 6-25-55