


STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 9 Twp. 23 Rge. (E) 17 (W)
Location as "NE/CNW/SW" or footage from lines SE SE SW
Lease Owner Colorado Oil Company
Lease Name Hutchinson "C" Well No. 3
Office Address 915 Union Natl. Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed February 14 1955
Application for plugging filed April 27 1970
Application for plugging approved April 28 1970
Plugging commenced June 13 1970
Plugging completed June 22 1970
Reason for abandonment of well or producing formation Depleted



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production August 31 1969
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Congl. Chert Depth to top 4237 Bottom Total Depth of Well 4400 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	268'	None
				5-1/2"	4399'	3382'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole to 4370', pushed plug to 4250' and ran sand & 5 sacks of cement. Loaded hole with water, shot pipe at 3480', 3388', worked pipe loose and pulled 107 joints. Halliburton pumped 5 sacks hulls, 20 sacks mud and 100 sacks of cement.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1970
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Knight Casing Pulling Co., Inc.
Address P. O. Box 405, Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bill K. Henrichs (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill K. Henrichs
915 Union Natl. Bldg., Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of July, 1970

Betty J. McEwen
Notary Public.

My commission expires February 19, 1973

15-145-00839-0000

DRILLERS LOG

Hutchinson "C"-3

Loc: SE SD SW

Sec: 9-23-17W

Pawnee County, Kansas

Company: Colorado Oil & Gas Corporation

Contractor: Honaker Drlg., Inc.

Comm: 1-24-55

Comp: 2-7-55

Elevation: 2100' D.F.

Total Depth: 4400'

Casing: 8-5/8" set @ 267'

5-1/2" set @ 4399'

0	130	Sand.	
130	430	Shale & Shells.	8-5/8" 24# casing set @
430	600	Red Bed.	267' w/ 175 sacks cement &
600	6600	Sand.	2 sacks calcium chloride.
660	1142	Red Bed, Shale, & Sand.	
1142	1175	Anhydrite.	
1175	2000	Shale & Shells.	
2000	2075	Lime & Shale.	
2075	2210	Shale & Lime.	
2210	2460	Lime & Shale.	
2460	3410	Shale & Lime.	
3410	3480	Broken Lime.	
3480	3645	Lime & Shale.	
3645	3693	Lime.	
3693	3820	Lime & Shale.	
3820	4220	Lime.	
4220	4246	Conglomerate.	
4246	4247	Lime.	
4247	4267	Conglomerate.	
4267	4295	Lime.	
4295	4320	Chert.	
4320	4345	Lime & Shale.	
4345	4400	Lime & Chert.	
4400		Rotary Total Depth.	5-1/2" casing cemented
			@ 4399' w/ 150 sacks
			cement.

RECEIVED
STATE CORPORATION COMMISSION
APR 28 1970
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is the true and correct copy of the above log, to the best of my knowledge.

R. H. Fisher

Subscribed and sworn to before me this 14th day of

February, 1955.

Leath P. Fisher
Notary Public

My Commission Expires: 6-25-55