

STATE OF KANSAS  
 STATE CORPORATION COMMISSION  
 200 Colorado Derby Building  
 Wichita, Kansas 67202

WELL PLUGGING RECORD  
 K.A.R.-82-3-117

15.145-00987-00-01

API NUMBER N/A

LEASE NAME Godfrey

TYPE OR PRINT  
 NOTICE: Fill out completely  
 and return to Cons. Div.  
 office within 30 days.

WELL NUMBER 1

330 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 7 TWP. 23S RGE. 17 (W) or (X)

LEASE OPERATOR Robinowitz Oil Company

ADDRESS 7130 S. Lewis, Suite 910, Tulsa, OK. 74136

COUNTY Pawnee

PHONE# (918) 481-7130 OPERATORS LICENSE NO. 6883

Date Well Completed 10-22-57

Character of Well SI

Plugging Commenced 11-17-88

(Oil, Gas, D&A, ~~SWD~~, Input, Water Supply Well)

Plugging Completed 11-17-88

The plugging proposal was approved on 10-24-88 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? 2 If not, is well log attached? yes

Producing Formation Arbuckle Depth to Top 4615 Bottom 5225 T.D. 5225

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Water	4615	5225	8 5/8	260	none
				5 1/2	4615	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.  
Set CIBP at 4450' dump one sack CMT 4450-4442. Spot 100 sacks 60-40' POZ 6% Gel 1154-0 thru TBG. squeeze 50 sacks of same blend down 5 1/2 thru perfs at 255' into 85/8X 5 1/2 annulus. Squeeze pressure 400 psi ISIP 250 psi

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B. J. Titan

RECEIVED  
 STATE CORPORATION COMMISSION  
 License No. 11-23-1988  
 NOV 23 1988

Address P.O. Box 4442 Houston

STATE OF Texas COUNTY OF Houston, ss.

CONSERVATION DIVISION  
 Wichita, Kansas

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Gary J. Miller  
 Gary Miller PE  
 (Address) 7130 S. Lewis, Suite 910 Tulsa, OK. 74136

SUBSCRIBED AND SWORN TO before me this 21st day of November, 19 88

Michael J. Wilcox  
 Notary Public

My Commission Expires: May 22, 1992