


5-149-00826-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pawnee County. Sec. 7 Twp. 23S Rge. 17W(E) (W)
Location as "NE/CNW/SW" or footage from lines NE SE NE
Lease Owner ALPINE OIL & ROYALTY CO., INC.
Lease Name Hazel Schartz Well No. 2
Office Address 1100 Bitting Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed December 11, 1954 19
Application for plugging filed February 17, 1958 19
Application for plugging approved February 18, 1958 19
Plugging commenced February 18, 1958 19
Plugging completed February 24, 1958 19
Reason for abandonment of well or producing formation Non-productive in
commercial quantities
If a producing well is abandoned, date of last production February 4 19 58
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot
Producing formation Misener Sand Depth to top 4259 Bottom _____ Total Depth of Well 4310 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	204'	Cemented
				5 1/2"	4309'	3169.39

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Sanded to 4245 feet - dumped 5 sacks cement with bailer
Pulled 90 joints of pipe and pumped 20 sacks mud through
casing - finished pulling pipe - pumped in 20 sacks mud and
100 sacks cement through surface pipe - removed 8 5/8"
plug container - checked in hole - cement was down 20 feet
from top - finished filling with cement.

RECEIVED
STATE CORPORATION COMMISSION

MAR 4 1958

CONSERVATION DIVISION
Wichita, Kansas

3-4-1958

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R & D Casing Pulling Company
Address Box 569, Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Thomas M. McCaul (employee or owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature) Thomas M. McCaul

1100 Bitting Building, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 19 58

Virginia Mundell
Notary Public.

My commission expires August 10, 1961

PLUGGING
FILE SEC. 7 T. 23 S. 17 W.
83 36

WELL LOG

15-145-068 26-0000

ALPINE OIL & ROYALTY CO., INC.

Commenced: 11-8-54

Contractor: Quaker Drilling Co., Inc.

Completed: 12-11-54

Hazel Schartz No. 2
NE SE NE Sec. 7-23S-17W
Pawnee County, Kansas

Elevation: 2073 K. B.

Production: 66 BOPD

Casing Record:

Set 204' of 8 5/8" with 90 sacks cement.
Set 4309' of 5 1/2" with 150 sacks cement.

(Figures Indicate the Bottom of Formations)

<u>FORMATIONS</u>	<u>DEPTH</u>	<u>FORMATION TOPS</u>	
Sand and Shale	123	Anhydrite	1105
Blue Shale & Shells	350	Heebner	3636 -1563
Red Bed	570	Brown Lime	3739 -1666
Sand	655	Lansing	3747 -1674
Shale, Shells, & Red Bed	970	Shaley Conglomerate	4171 -2098
Shale and Shells	1105	Cherty Conglomerate	4200 -2127
Anhydrite	1140	Mississippian	4209 -2136
Shale	1245	Misener Sand	4259 -2184
Shale & Shells	1480	Viola	4296 -2223
Shale	1594	Rotary Total Depth	4310 -2237
Lime and Shale	3705		
Lime	3935		
Lime and Shale	3985		
Lime	4070		
Lime and Shale	4180		
Lime	4245		
Chert and Lime	4310		

RECEIVED
OIL CORPORATION

MAR 4 1958

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above is a true and correct copy of the Drillers Log of the well drilled in the NE SE NE of Section 7, Township 23 South, Range 17 West, Pawnee County, Kansas.

QUAKER DRILLING CO., INC.

By: *Thomas M. M. Cline*
President

SUBSCRIBED AND SWORN to before me this 13th day of January, 1955.

Regina Mendell
Notary Public

My Commission Expires:
August 10, 1957

DRILLING
7-23S-17W
83 LINE 36