


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.



Locate well correctly on above Section Plat

Pawnee County. Sec. 7 Twp. 23S Rge. (E) 17 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines 2310' fr EL & 330' fr NL, SE/4
Lease Owner Phillips Petroleum Co.
Lease Name Godfrey "A" Well No. 8
Office Address Box 287 - Great Bend, Kans.
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed Oct. 20 19 55
Application for plugging filed May 23, 1963 19
Application for plugging approved May 29, 1963 19
Plugging commenced June 5 19 63
Plugging completed June 7 19 63
Reason for abandonment of well or producing formation Unprofitable to operate

If a producing well is abandoned, date of last production Feb. 6 19 63
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Basal Penn. Cong. Depth to top 4214' Bottom 4336' Total Depth of Well PB 4346 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Conglomerate	Oil	4214	4336	9-5/8"	857.93'	None
				7"	4409.14'	3129'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Checked hole, sanded to 4200', and dumped 5 sacks cement @ 4200' with dump bailer. Pulled 7" casing to 500' and pumped 20 sacks of gel mud. Pulled 7" casing to 350' and pumped in 20 sacks of cement. Pulled 7" casing to 160' and pumped in 20 sacks cement. Pulled balance of 7" casing, bailed hole to 25' and ran 10 sacks of cement from 25' to base of cellar.

Knight Casing Pulling Co. - Plugging Contractor

RECEIVED
STATE CORPORATION COMMISSION

JUN 19 1963

6-19-1963
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Address

STATE OF Kansas, COUNTY OF Barton, ss.

M. E. Michael (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. E. Michael
Box 287 - Great Bend, Kans.
(Address)

SUBSCRIBED AND SWORN to before me this 18th day of June, 19 63

My commission expires Nov. 18, 1965

Joseph M. Biel Notary Public.

15-145-60824-0000

FORMATION RECORD

Godfrey A-8

0	230	Sand, shale
230	415	Shale
415	761	Shale, red bed & shale
761	1000	Red bed & shale
1000	1072	Red bed, Anhy.
1072	1350	Red bed, shale, Anhy.
1350	1663	Shale, shells, salt
1663	1920	Salt & shale
1920	2143	Lime & shale
2143	2431	Lime
2431	2726	Lime & shale
2726	3075	Shale
3075	3583	Lime & shale
3583	3670	Lime
3670	3759	Lime & shale
3759	4094	Lime
4094	4184	Lime & shale
4184	4313	Lime & chert
4313	4327	Lime
4327	4382	Lime & chert

RECEIVED
STATE CORPORATION COMMISSION

JUN 19 1963

CONSERVATION DIVISION
Wichita, Kansas