

15-145-00870-0000

C. E. ...

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
1001 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 7 Twp 23S Rge. 17W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NE SE
Lease Owner Phillips Petroleum Company
Lease Name Godfrey-A Well No. 4
Office Address Box 287, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed August, 1955 19
Application for plugging filed 1-23-65 19
Application for plugging approved 1-25-65 19
Plugging commenced 2-9-65 19
Plugging completed 2-9-65 19
Reason for abandonment of well or producing formation Unprofitable

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 1-15-65 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Box 326, Hays, Kansas
Producing formation Congl Depth to top 4196 Bottom Total Depth of Well 4373 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
LKC		3747	4037	9-5/8	861	
Marmaton		4046		7"	4398'	2030'
Cherokee		4177				
Congl		4196				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Spotted 25 sx mud 4185' to 500', 30 sx cmt 500' to 425', mud to 170', 30 sx cmt 170' to 100', mud to 15', 10 sx cmt 15' to surface. Job completed 12 noon 2-9-65. P&A.

RECEIVED
STATE CORPORATION COMMISSION

FEB 11 1965

2-11-1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Company
Address Great Bend, Kansas

STATE OF Kansas COUNTY OF Barton, ss.
M. E. Michael Area Supt. (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. E. Michael
Box 287, Great Bend, Kan.
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of February 19 65

My commission expires 11-18-65

Joseph M. Deal
Notary Public

15-145-00812-0000
 GP

EXPLORATION RECORD

Lease Godfrey-A

Well 4

Formation Name	Top	Base	Remarks
Sand, shale and shells	0	236	
Shale and shells	236	540	
Sand, shale and redbed	540	806	
Redbed and shale	806	1030	
Shale	1030	1074	
Shale, shells and anhydrite	1074	1394	
Shale and shells	1394	1650	
Shale, shells and salt	1650	1853	
Shale and lime streaks	1853	2028	
Lime and shale	2028	2210	
Lime	2210	2405	
Lime and shale	2405	2646	
Shale and lime streaks	2646	2754	
Shale	2754	3001	
Lime and shale	3001	3136	
Shale	3136	3281	
Lime and shale	3281	3436	
Lime	3436	3668	
Lime and shale	3668	3747	
Lime	3747	4198	
Shale	4198	4207	**Cored
Lime and shale	4207	4229	**Cored
Shale	4229	4246	**Cored
Lime and shale	4246	4248	**Cored
Sand	4248	4249	**Cored
Shale	4249	4292	**Cored
Sand, lime and chert	4292	4320	
Lime and chert	4320	4373*	
FORMATION TOPS SAMPLE			
Heebner	3634		
Toronto	3648		
Douglas	3665		
Brown Limestone	3739		
LKC	3747		
Base LKC	4037		
Marmaton	4046		
Cherokee	4177		
Cherty Viola	4335		
Crystalline Viola	4353		
RTD	4373		
Cable Tool TD PB	4326		
			** Not penetrated at 4373' TD.
			** See Daily report detailed and Form 864-D Core Record.

RECEIVED
 STATE CORPORATION COMMISSION

FEB 11 1965

CONSERVATION DIVISION
 Wichita, Kansas