


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 10 Twp. 23 Rge. 17 (E) (W) X
Location as "NE/CNW/SW" or footage from lines NE SW NW
Lease Owner Rock Island Oil & Ref. Co., Inc.
Lease Name Anderson "B" Well No. #4
Office Address 321 W. Douglas, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 12-8-64 19
Plugging completed 12-16-64 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
						2627.96'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Made plug back with sand to 4200', mixed and ran 4 sacks cemen thru dump baler.
Squeezed hole with 35 sacks gel and 100 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 18 1964

12-18-1964

CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Southwest Casing Pulling Co., Inc.
Address Box 364, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Southwest Casing Pulling Co., Inc. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. C. Spencer Sec.
Box 364, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17 day of December, 1964

My commission expires 24 October 1968

Sidney D. Miller
Notary Public.

Send to
KCC

15-145-61338-0000

Rock Island O & L
ANDERSON "B"-4

NE/4 SW/4 NW/4 of Section 10-23S-17W Pawnee County, Kansas

Rigged up Rotary Tools 8/11/55

Ran 8 Jts. (247') 8 5/8" Surface Pipe set at 246'. Cemented with 175 sacks bulk cement.

Tore down Rotary Tools 8/26/55

Ran 136 Jts. (4292') 5 1/2" 8 Rd Thd New 15 1/2" Pipe set at 4279'. Cemented with 150 sacks Posmix

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	
Shale & sand	0'	247'	
Gray shale & shells	247	370	
Sand & redbed	370	688	
Redbed & shale	688	1136	
Anhydrite	1136	1169	
Shale & shells	1169	1930	
Shale w/lime streaks	1930	2185	
Shale & lime	2185	2325	
Lime	2325	2340	
Lime & shale	2340	2875	
Shale w/lime streaks	2875	2976	
Shale & lime	2976	3190	
Shale w/lime streaks	3190	3302	
Shale & lime	3302	3743	
Lime	3743	4061	
Lime w/shale streaks	4061	4121	
Lime	4121	4215	
Conglomerate	4215	4280	TD

RECEIVED
STATE CORPORATION COMMISSION

DEC 24 1964

CONSERVATION DIVISION
Wichita, Kansas

I, W. M. Barnett, do hereby certify that the foregoing log is true and correct, to the best of my knowledge and belief.

W. M. Barnett

Subscribed and sworn to before me this 31st day of August, 1955.

James Swaney

My commission expires: July 29, 1957

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
500 East Murdock, Wichita, Kansas

15-145-61338-0000


COPY

Company: WOOD RIVER OIL & REFINING CO.
Farm: Anderson "B" No. 4

SEC. 10 T. 23 R. 17W
NE SW NW

Total Depth. 4280
Comm. 8-11-55 Comp. 8-26-55
Shot or Treated.
Contractor: D & M Drilling Co., Inc.
Issued. 11-5-55

County Pawnee
KANSAS



Elevation. 2104 RB

Production Flow 639 BOPD

CASING:

8 5/8 @ 246' w/ 175 sx cmt.
5 1/2 @ 4279' w/ 150 sx cmt.

Figures indicate Bottom of Formations.

shale & sand	247
gray shale & shells	370
sand & red bed	688
red bed & shale	1136
anhydrite	1169
shale & shells	1930
shale w/ lime streaks	2185
shale & lime	2325
lime	2340
lime & shale	2875
shale w/ lime streaks	2976
shale & lime	3190
shale w/ lime streaks	3302
shale & lime	3743
lime	4061
lime w/ shale streaks	4121
lime	4215
conglomerate	4280
Total Depth	

TOPS:	
Topeka	3578
Heebner	3658
Douglas	3689
Brown lime	3767
Lansing	3775
Shaley Conglomerate	4180
Cherty Conglomerate	4214

RECEIVED
STATE CORPORATION COMMISSION

FEB 22 1966

OBSERVATION DIVISION
Wichita, Kansas