


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Pawnee County, Sec. 10 Twp. 23 Rge. 17 (E) (W)
Location as "NE/CNW/SW" or footage from lines NW NE NW
Lease Owner Rock Island Oil & Refining
Lease Name Anderson B Well No. 3
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole)
Date well completed 19____
Application for plugging filed 19____
Application for plugging approved 19____
Plugging commenced 1/3/67 19____
Plugging completed ~~1/3/67~~ 1/13/67 19____
Reason for abandonment of well or producing formation depleted.

If a producing well is abandoned, date of last production 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4292' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	268	none
				5 1/2	4290	2593

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Raised mast, checked hole to 4260'. Ran sand from 4260 to 4150', mixed and ran 5 sacks of cement. Rigged up over 5 1/2" casing, worked tension ~~22~~ to 20". Shot pipe at 2587', worked pipe loose and pulled 30 joints of R2 and 3 pipe. Pulled 10 joints of 5 1/2". Pulled 37 joints of 5 1/2", loaded junk rack. Lowered mast, racked unit. Pumped 100 sacks of cement and 25 sacks mud.

RECEIVED
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

JAN 23 1967

1-23-1967
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 17 day of Jan, 1967

My commission expires Oct 22-1970
Notary Public.

ANDERSON "B" - 3

NW/4 NE/4 NW/4 of Section 10-23S-17W Pawnee County, Kansas

Rigged up Rotary Tools 7/27/55

Ran 9 Jts. (269') 8 5/8" 8 Rd Thd 24#
New Casing set at 268'. Cemented with
175 sacks common cement.

Tore down Rotary Tools 8/10/55

Ran 130 Jts. (4312') 5 1/2" New Casing
set at 4289.50'. Cemented with 150
sacks common cement.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface clay and sand	0'	60'
Shale & shells	60	240
Shale	240	470
Shale & sand	470	750
Redbed & shale	750	1110
Anhydrite	1110	1145
Shale & shells	1145	1240
Shale, shells w/lime streaks	1240	1523
Shale & shells	1523	1680
Shale w/lime streaks	1680	1898
Shale & lime	1898	2035
Lime w/shale streaks	2035	2210
Lime & shale	2210	2410
Lime, sand & shale	2410	2481
Lime & shale	2481	2750
Shale w/lime streaks	2750	3001
Shale & lime	3001	3875
Lime	3875	4096
Lime & shale	4096	4171
Lime & chert	4171	4195
Conglomerate & chert	4195	4290 TD

RECEIVED
STATE CORPORATION COMMISSION
DEC 27 1966
CONSERVATION DIVISION
Wichita, Kansas

I, W. M. Barnett, do hereby certify that the foregoing log is true and correct, to the best of my knowledge and belief.

W. M. Barnett

Subscribed and sworn to before me this 11th day of August, 1955.

June Swaney

My commission expires: July 29, 1957