

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Return to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Pawnee County, Sec. 10 Twp. 23 Rge. (E) 17 (W)

Location as "NE/CNW/SW" or footage from lines SW SW SW
Lease Owner Colorado Oil Company
Lease Name Anderson Well No. 1
Office Address 915 Union National Bldg., Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed April 30 1955
Application for plugging filed October 27 1969
Application for plugging approved October 28 1969
Plugging commenced November 11 1969
Plugging completed December 15 1969
Reason for abandonment of well or producing formation Depleted

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production September 30 1969
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Massey
Producing formation Conglomerate Chert Depth to top 4218 Bottom Total Depth of Well 4378 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	254'	None
				5-1/2"	4374'	3240'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked bottom, ran sand to 4200' and dumped 5 sacks of cement.
Loaded hole, shot pipe at 3347', lost wire line, fished wire line.
Loaded hole, shot pipe at 3255', 3160', 3060', worked pipe loose and pulled 100 joints. Halliburton pumped 5 sacks hulls, 20 sacks gel and 100 sacks of cement to plug well.

PLUGGING COMPLETE.

RECEIVED 12-24-1969
STATE CORPORATION COMMISSION
DEC 24 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Knight Casing Pulling Co., Inc.
Address Chase, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Bill K. Henrichs (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill K. Henrichs [Signature]
915 Union National Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of December, 1969

My commission expires Feb. 19, 1973
Betty J. McElwain Notary Public.

DRILLERS LOG

15-145-01333-0000

Anderson Well No. 1
Loc: SW SW SW
Sec: 10-23-17W
Pawnee County, Kansas
Company: Colorado Oil & Gas Corp.

Comm: 3-30-55
Comp: 4-22-55
Rotary Total Depth: 4378'
Casing: 8-5/8" set @ 254'
5-1/2" set @ 4377'

0	50	Sand & Clay.	
50	100	Sand & Shale.	
100	255	Shale & Shells.	8-5/8" casing set @ 254'
255	390	Shale.	cemented w/ 175 sacks cement
390	540	Red Bed.	and 200# calcium chloride
540	610	Sand.	with 2 plugs.
610	1145	Shale & Shells.	
1145	1190	Anhydrite.	
1190	2000	Shale & Shells.	
2000	3470	Lime & Shale.	
3470	3700	Lime.	
3700	3780	Shale & Broken Lime.	
3780	4145	Lime.	
4145	4200	Lime & Shale.	
4200	4230	Lime.	
4230	4250	Lime.	
4250	4252	Chert & Shale.	
4252	4378	Lime & Chert.	
4378		Rotary Total Depth.	5-1/2" casing set @ 4377'
			cemented w/ 175 sacks
			cement.

I certify that this is the true and correct copy of the above log, to the best of my knowledge.

H. Forbes

Subscribed and sworn to before me this 26th day of April, 1955.

Robert P. Fisher
Notary Public

My Commission Expires: 6-25-55

NOTARY PUBLIC
COMMISSION EXPIRES
JUN 25 1955
STATE OF KANSAS