

KANSAS

STATE CORPORATION COMMISSION

15-145-00837-0000

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

NOV 12 1973
11-12-1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name A. L. Abercrombie, Inc.

Complete Address 801 Union Center, Wichita, Kansas 67202

Lease Name Hutchinson "C" Well No. 1

Location NW NW SW Sec. 9 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4370'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364 Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 10 :30 A Day 8 Month 11 Year 1973

The above well was plugged as follows:

Total Depth 4370' 8 5/8 csg set at 235' cwc 175 sk.

5 1/2 csg set at 4368' ow 100 sk cem.

5 1/2 csg FBTD 4285' & perf. (4210-4220)

Filled 5 1/2 csg W/sd (4190-4285) dumped 5 sk cem W/dump bailer. (4155-4190)

Cutoff and recovered 3400' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, released plug and

pumped 100 sk comm cem. W/2% gel by Sun Cementing Co. Max PP 250# SIP 150#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bio G Messy
Well Plugging Supervisor

DATE 11/12/73

INV. NO. 8152-10