

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 26 1969 5-26-1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company 15-145-66858-0001

Complete Address: 915 Union National Bldg., Wichita, Kansas 67202

Lease Name Hutchinson "E" Well No. 6

Location G NW Sec. 9 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4357

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 5:30P Day 23 Month 5 Year 1969

The Above well was plugged as follows:

Total Depth 4357 8 5/8 csg set at 246' cwc 175 sk.

5 1/2 csg set at 4356 cw 175 sk cmt.

5 1/2 csg PBD 4280 with top perf. (4216)

Filled 5 1/2 csg W/sd (4200-4280) Dumped 5 sk cmt W/dump bailer/ (4160-4200)

Shutoff and recovered 3210' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 5/27/69
INV. NO. 9825-U