

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 19 1974
4-19-1974

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name A.L. Abercrombie, Inc. 15-145-00856-0000

Complete Address 801 Union Center, Wichita, Kansas 67202

Lease Name Hutchinson "E" Well No. 4

Location NE NE NW Sec. 9 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4377'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 3:30 P Day 17 Month 4 Year 1974

The above well was plugged as follows:

Total depth 4377' 8 5/8 csg set at 245' cwc 225 sk.

5 1/2 csg set at 4376' cw 175 sk cem.

5 1/2 csg PBT 4364 & perf. (4203)

Filled 5 1/2 csg with sand (4000-4364) dumped 4 sk cem W/dump bailer. (4000-3970)

Cutoff and recovered App. 2670' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls, -released 8 5/8 plug

& pumped 100 sk comm cem. 2% gel, by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing
Well Plugging Supervisor

DATE 4/23/74

INV. NO. 8955-W