

KANSAS

AL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

6-24-1970
RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-145-66855-0000

Operator's Full Name Colorado Oil Company

Complete Address 915 Union National Bldg., Wichita, Kansas

Lease Name Hutchinson "E" Well No. 3

Location NW NW NW Sec. 9 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4305'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 6:45P Day 22 Month 6 Year 1970

The above well was plugged as follows:

Total Depth 4305' 8 5/8 csg set at 250' cwc 175 sk.

5 1/2 csg set at 4304' cw 175 sk

5 1/2 csg perf. (4184)

Set wood plug 4150' -- Sd (4135-4150) Dumped 5 sk cmt W/dump bailer. (4100-4135)

Cutoff and recovered 3140' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Bo G. Massey
Well Plugging Supervisor

INVOICED

DATE 6/25/70

INV. NO. 2109-W