

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

15-143-00854-0000

RECEIVED 1-16-1970  
STATE CORPORATION COMMISSION  
JAN 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company

Complete Address 915 Union National Bldg., Wichita, Kansas

Lease Name Hutchinson "E" Well No. 2

Location SE SE NW Sec. 9 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4360'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 2:30P Day 14 Month 1 Year 1970

The above well was plugged as follows:

Total Depth 4360' 8 5/8 csg set at 240' cwc.

5 1/2 csg set at 4359' cw 175 sk cmt.

5 1/2 csg PBTB 4303' and perf. (4200-4236)

Filled 5 1/2 csg W/sd (3950-4303) Dumped 5 sk cmt W/dump bailer. (3910-3950)

Cutoff and recovered 2656' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/500 lbs hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]  
Well Plugging Supervisor

DATE 1/16/70  
INV. NO. 1264-4