

15-145-60853-0000 R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
APR 19 1974  
CONSERVATION DIVISION  
Wichita, Kansas

4-19-1974

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name A. L. Abercrombie, Inc.

Complete Address 801 Union Center, Wichita, Kansas 67202

Lease Name Hutchinson "E" Well No. 1

Location SW SW NW Sec. 9 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4354'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 1:30 P. Day 17 Month 4 Year 1974

The above well was plugged as follows:

Total Depth 4354' 8 5/8 csg set at 256' cwc 225 sk.

5 1/2 csg set at 4353' cw 175 sk cem.

5 1/2 csg PBSD 4321' & perf. (4200)

Set 5 1/2 wood plug at 4000' -poured 25' sand -dumped 4 sk cem W/dump bailer. (3975-3945)

Cutoff and recovered N/2700' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -released 8 5/8 plug

and pumped 50 sk cement by Sun Cementing Co.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 4/23/74

INV. NO. 8954-W

Signed: Geo F. Massey  
Well Plugging Supervisor