

15-145-00852-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1970
CONSERVATION DIVISION
Wichita, Kansas
6-24-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company

Complete Address 915 Union Nat'l Bldg., Wichita, Kansas 67202

Lease Name Hutchinson "D" Well No. 11

Location E/2 E/2 NE Sec. 9 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4325

Abandoned Oil Well XXX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 8P 22 Day 22 Month 6 Year 1970

The above well was plugged as follows:

Total Depth 4325' 8 5/8 csg set at 246' cwc 175 sk.

5 1/2 csg set at 4324' cw 175 sk cmt.

5 1/2 csg PBTB 4237' with top perf. (4232)

Set 5 1/2 wood plug at 3800' - Poured sd (3740-3800) Dumped 5 sk cmt W/dmp Bl. (3700-40)

Cutoff and recovered 3180' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Mansur
Well Plugging Supervisor

DATE 6/25/70

INV. NO. 2108-44