

KANSAS



STATE CORPORATION COMMISSION

15-145-00851-0000

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 26 1969
CONSERVATION DIVISION
Wichita, Kansas

5-26-1969

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company

Complete Address: 915 Union Nat'l Bldg., Wichita, Kansas 67202

Lease Name Hutchinson "D" Well No. 10

Location C N/2 N/2 NE Sec. 9 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4303

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 4P Day 23 Month 5 Year 1969

The Above well was plugged as follows:

Total Depth 4303 8 5/8 csg set at 244' cwc 175 sk.

5 1/2 csg set at 4302 cw 175 sk cmt.

5 1/2 csg PBTD 4274 with top perf. (4185)

Filled 5 1/2 csg W/sd (4170-4274) Dumped 5 sk cmt W/dump bailer. (4130-4170)

Shutoff and recovered 3200' of 5 1/2 csg.

~~Pumped thru 8 5/8" plug container~~ Pumped thru 8 5/8" plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 5/27/69

INV. NO. 9824-W