

KANSAS

Form CP-3
Rev. 6-4-68

4
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1970 6-24-1970
CONSERVATION DIVISION
Wichita, Kansas

15-145-60846-0000

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company
Complete Address 915 Union National Bldg., Wichita, Kansas 67202
Lease Name Hutchinson "D" Well No. 5
Location S/2 S/2 SE Sec. 9 Twp. 23 Rge. (E) (W) 17
County Pawnee Total Depth 4379
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Knight Casing Pulling Co.
Address Box 405 Chase, Kansas License No. 436
Operation Completed: Hour 12:30 P.M. Day 22 Month 6 Year 1970

The above well was plugged as follows:

Total Depth 4379' 8 5/8 csg set at 244' cwc 175 sk.
5 1/2 csg set at 4378' cw 175 sk cmt.
5 1/2 csg perf. (4230)
Filled 5 1/2 csg W/sd (4200-4379) Dumped 5 sk cmt W/dump bailer. (4160-4200)
Cutoff and recovered 3400' of 5 1/2 csg.
Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Murray
Well Plugging Supervisor

DATE 6/25/70
INV. NO. 2107-4