

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
APR 5 1971
CONSERVATION DIVISION
Wichita, Kansas 4-5-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company 15-145-00844-006⁰
Complete Address 915 Union National Bldg., Wichita, Kansas 67202
Lease Name Hutchinson "D" Well No. 3
Location SW SW SE Sec. 9 Twp. 23 Rge. (E) (W) 17
County Pawnee Total Depth 4378'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Knight Casing Pulling Co,
Address Chase, Kansas License No. 436
Operation Completed: Hour 12:15 P Day 2 Month 4 Year 1971

The above well was plugged as follows:

Total Depth 4378' 8 5/8 csg set at 251' cwc 200 sk.
5 1/2 csg set at 4377' cw 175 sk cmt.
5 1/2 csg perf. (4250)
Filled 5 1/2 csg W/sd (4200-4378') Dumped 5 sk cmt W/dump bailer. (4160-4200)
Cutoff and recovered 3300' of 5 1/2 csg.
Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, released plug and
pumped 100 sk 50-50 poz cmt W/1% added gel.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Manning
Well Plugging Supervisor

DATE 4/6/71
INV. NO. 3500-4