

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

1-16-1970

RECEIVED
STATE CORPORATION COMMISSION
JAN 16 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company 15-149-00843-0000

Complete Address 915 Union Nat'l Bldg., Wichita, Kansas 67202

Lease Name Hutchinson "D" Well No. 2

Location SW SW NE Sec. 9 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4360'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Chase, Kansas Box 405 License No. 436

Operation Completed: Hour 3.30P Day 14 Month 1 Year 1970

The above well was plugged as follows:

total Depth 4360' 8 5/8 csg set at 220' cwc 175 sk.

5 1/2 csg set at 4359' cw 175 sk cmt.

5 1/2 csg PBTD 4329 with top perf. (4228)

Filled 5 1/2 csg W/sd (4200-4329) Dumped 5 sk cmt W/dump bailer. (4160-4200)

Cutoff and recovered 3150' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/500 lbs hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ben F. Messing
Well Plugging Supervisor

DATE 1/16/70
INV. NO. 1263-u