

KANSAS

Handwritten initials

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUN 24 1970

CONSERVATION DIVISION
Wichita, Kansas

6-24-1970

15-145-06842-0000

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company

Complete Address: 915 Union National Bldg., Wichita, Kansas

Lease Name Hutchinson "C" Well No. 6

Location SW SW SW Sec. 9 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4392

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Chase, Kansas License No. 436

Operation Completed: Hour 4:15 P Day 22 Month 6 Year 1970

The Above well was plugged as follows:

Total Depth 4392' 8 5/8 csg set at 242' cwc 175 sk.

5 1/2 csg set at 4391' cw 175 sk cmt.

5 1/2 csg PBTD 4362' with perf, (4232-4306)

Filled 5 1/2 csg W/sd (4200-4362) Dumped 5 sk cmt W/dump bailer. (4160-4200)

Cutoff and recovered 3380' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. Massey
Well Plugging Supervisor

DATE 6/25/70
INV. NO. 2105-W