

15-145-80841-0001

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 24 1970
CONSERVATION DIVISION
Wichita, Kansas

6-24-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company

Complete Address 915 Union National Bldg., Wichita, Kansas 67202

Lease Name Hutchinson "C" Well No. 5

Location W/2 W/2 SW Sec. 9 Twp. 23 Rge. (E) (W) 17

County Pawnee Total Depth 4381

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling Co.

Address Chase, Kansas License No. 436

Operation Completed: Hour 5:30 P Day 22 Month 6 Year 1970

The above well was plugged as follows:

Total Depth 4381' 8 5/8 csg set at 248' cwc 175 sk.

5 1/2 csg set at 4380' cw 175 sk cmt.

5 1/2 csg PBT 4350' with top perf. (4229-4232)

Filled 5 1/2 csg W/sd (4200-4350) Dumped 5 sk cmt W/dump bailer. (4150-4200)

Cutoff and recovered 1900' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 200 sks gel W/5 sk hull, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ben F. Massey
Well Plugging Supervisor

DATE 6/25/70

INV. NO. 2104-W